





[®] Light Engineered Displays, Inc.

Graphic Annunciators * Water Leak Detection Fireman's Smoke Control Panels * ARA Systems

109 Portwatch Way Wilmington, N.C. 28412 Phone: (800) 251-2512 Fax: (800) 251-9878 Internet: www.ledinc.com Email: sales@ledinc.com







Remote Alarm Indicator

Part No.	Description	Vol
RL-1	LED	1-8
RL-2	LED w/ resistor	24
RL-3	Incandescant	24


/oltage I-8 Volt Polarized 24 Volt Polarized 24 Volt Non-polar Current 10 Milliamp 20 Milliamp 40 Milliamp





Abort Station


Part No. Description AS-1 Abort Station w/ one N.O. contact Red spring-loaded mushroom pushbutton.



Disconnect Switch

DS-1 Switch is SPST Maintained w/ screw terminals. Mounted on single gang brushed SS plate. Contacts rated for 5 amps, 115 VAC.





Fire Fighter Telephone Jack

Description
Standard tip & ring - No auxillary contacts.
Standard tip & ring w/ 1 NO contact.
Standard tip & ring w/ 2 aux. contacts.

NOTE: Custom wording and special features are available. Contact factory for details and minimum order requirements.